

ADDENDUM NO. 1
REQUEST FOR PROPOSALS
New Jersey Licensed Well Driller
Harrison Avenue Landfill
E. State Street & Harrison Avenue, Camden, New Jersey

November 1, 2017

The Respondent must complete and return the *Acknowledgement of Receipt of Addenda* form with their proposal. Failure to complete and return the *Acknowledgement of Receipt of Addenda* form shall result in rejection of the proposal.

Where this Addendum and the Request for Proposals may differ, the Addendum prevails.
This Addendum hereby modifies the Request for Proposals as follows:

1. Clarifications

Responses to questions provided by prospective Respondents are provided below. All Respondents are hereby notified to read the responses carefully as they clarify the work that is covered in the Request for Proposals. Responses from CRA are printed in red.

- 1) When is the well abandonment task expected or needed to be performed and completed?

“The Contractor shall agree to commence work immediately upon receipt of Notice to Proceed from the CRA and diligently pursue the work as per a schedule to be determined by the CRA’s Representative and the Contractor prior to the commencement of the work.” (Page 10).

“The Contractor will locate and decommission [the] wells prior to the commencement of reconstruction activities, which are scheduled to begin in March 2018.” (Page 15).

It is expected that Notice to Proceed may be issued by CRA to the successful respondent in late January 2018. Therefore, it is anticipated that well abandonments shall take place in January-February 2018.

- 2) When is the well installation task expected or needed to be performed and completed?

“As work is completed on the reconstruction of the landfill, up to 17 new wells will be installed as directed by the CRA Representative...” (Page 17). It is unknown when NJDEP will complete the work on the landfill, however installation of wells are expected to begin within 10-12 months following the commencement of NJDEP construction activities, which are scheduled to begin in March 2018.

- 3) Is soil sampling / split spoon sampling required during well installations?

No.

- 4) Assuming equipment decontamination is required between well locations, are the fluids generated expected to be contained or allowed to be discharged onto the ground?

Decontamination fluids will be containerized and disposed off-site as per the waste management requirements of the RFP.

- 5) What drilling method is required or is that the choice of the Licensed Driller?

The drilling method will be proposed by the Licensed Driller and must be approved by CRA.

- 6) Page 17, Task 2, B., 4. - Please elaborate on what is expected from the Driller on this topic. Is it the Drillers task to contain, manage, test and ultimately dispose of investigative derived wastes (drill cuttings, drill mud, decontamination and development fluids) to a licensed off-site disposal facility?

Yes.

What classification should be assumed.....non-hazardous or hazardous?

Non-hazardous.

ACKNOWLEDGMENT OF RECEIPT OF ADDENDA

The undersigned Bidder hereby acknowledges receipt of the following Addenda:

| Addendum Number | Dated | Acknowledge Receipt with Initials |
|-----------------|-------|--------------------------------------|
| _____ | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |
| _____ | _____ | _____ |

No addenda were received

ACKNOWLEDGED FOR:

(Name of Bidder)

BY:

(Signature of Authorized Representative)

PRINT NAME & TITLE:

COMPANY:

DATE:
